

AD-A101 548

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/6 13/13
NATIONAL DAM SAFETY PROGRAM, EAST HIGHLAND LAKE DAM (NJ 00288).--ETC(U)
JUL 81 A PERERA DACW61-79-C-0011

UNCLASSIFIED

DAEN/NAP-53842/NJ00288-81/ NL

1 OF 1
AD A
10:548

END
DATE
FILMED
8-81
DTIC

AD A101548

HUDSON RIVER BASIN
TRIBUTARY TO WARWICK CREEK
SUSSEX COUNTY
NEW JERSEY

EAST HIGHLAND LAKE DAM

NJ 00288

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM

DACW 61-79-C-0011



APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

THIS DOCUMENT IS BEST QUALITY AVAILABLE
THE COPY CONTAINED HEREIN IS THE BEST AVAILABLE COPY
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

REP. NO: DAEN/NAP-53842/NJ00288-81/07

JULY 1981

*Original contains color
plates. All DTIC reproductions
will be in black and
white.

81 7 15 045

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER DAEN/NAP 53842/NJ00288-81/07	2. GOVT ACCESSION NO. AD-A101 548	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program East Highland Lake Dam Sussex County, NJ		5. TYPE OF REPORT & PERIOD COVERED FINAL
7. AUTHOR(s) Perera, Abraham P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Louis Berger Assoc. 100 Halstead St. East Orange, NJ 07019		8. CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection Division of Water Resources P.O. Box CM029 Trenton, NJ 08625		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106		12. REPORT DATE July 1981
		13. NUMBER OF PAGES 50
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) National Dam Safety Program. East Highland Lake Dam (NJ 00288). Hudson River Basin. Tributary to Warwick Creek, Sussex County, New Jersey. Phase 1 Inspection Report.		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams National Dam Safety Program Embankments East Highland Lake Dam, N.J. Visual Inspection Erosion Structural Analysis Spillways		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

NOTICE

**THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.**



IN REPLY REFER TO
NAPEN-N

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

①

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

10

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for East Highland Lake Dam, Sussex County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, East Highland Lake Dam, initially listed as a high hazard potential structure but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition and the spillway is considered adequate. To ensure the adequacy of the structure the following remedial actions are recommended:

a. The eroded areas and displaced riprap on the upstream face of the dam should be filled and compacted with suitable embankment material and the riprap repositioned or replaced within thirty days from the date of approval of this report.

b. The following remedial actions should be initiated within six months from the date of approval of this report:

(1) Remove all trees and brush from the dam, refill and regrade the dam crest, and reestablish a firm grass cover over the entire embankment.

(2) Debris should be removed from the spillway and downstream channel.

(3) The blow-off gate valve should be repaired and tested, the manhole cover replaced, the displaced block at the top of the manhole repaired and the debris therein removed.

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

NAPEN-N

Honorable Brendan T. Byrne

(4) The deteriorated concrete at the spillway should be repaired.

(5) The drain pipe should be cleared of accumulated silt and debris.

c. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

d. An emergency action plan and warning system should be developed which outlines actions to be taken to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Courter of the Thirteenth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.


Sincerely,

1 Incl
As stated

for Kenneth R. Mason, Major CE, DE
JAMES G. TON
Colonel, Corps of Engineers
Commander and District Engineer

Copies furnished:
Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625



EAST HIGHLAND LAKE DAM (NJ00288)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 24 March 1981 by Louis Berger and Associates, Inc. under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

East Highland Lake Dam, initially listed as a high hazard potential structure but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition and the spillway is considered adequate. To ensure the adequacy of the structure the following remedial actions are recommended:

a. The eroded areas and displaced riprap on the upstream face of the dam should be filled and compacted with suitable embankment material and the riprap repositioned or replaced within thirty days from the date of approval of this report.

b. The following remedial actions should be initiated within six months from the date of approval of this report:

(1) Remove all trees and brush from the dam, refill and regrade the dam crest, and reestablish a firm grass cover over the entire embankment.

(2) Debris should be removed from the spillway and downstream channel.

(3) The blow-off gate valve should be repaired and tested, the manhole cover replaced, the displaced block at the top of the manhole repaired and the debris therein removed.

(4) The deteriorated concrete at the spillway should be repaired.

(5) The drain pipe should be cleared of accumulated silt and debris.

c. The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam within one year from the date of approval of this report.

d. An emergency action plan and warning system should be developed which outlines actions to be taken to minimize the downstream effects of an emergency at the dam within six months from the date of approval of this report.

APPROVED:

for *Kenneth R. Moore*, DC
JAMES G. TON
Colonel, Corps of Engineers
Commander and District Engineer

DATE:

1 July 1981

PHASE I REPORT
NATIONAL DAM INSPECTION PROGRAM

Name of Dam East Highland Lake Dam Fed ID# NJ 00288
NJ ID# 22-154

State Located New Jersey
County Located Sussex
Coordinates Lat. 4110.5 - Long. 7438.2
Stream Tributary to Warwick Creek
Date of Inspection March 24, 1981

ASSESSMENT OF
GENERAL CONDITIONS

East Highland Lake Dam is considered to be in fair overall condition and has a spillway capacity that will accommodate the 100-year design flood. It is recommended that the dam be evaluated within the framework of the significant hazard classification since its failure could result in damage to several residences and a local road immediately downstream. Remedial work requiring immediate attention includes the repair of the eroded portions of the embankment and replacement of the riprap in those areas. Repairs to be made in the near future include removal of trees and brush from the dam; removal of debris from the spillway, downstream channel, gate valve manhole, and drain pipe; repair of all deteriorated concrete at the spillway and manhole; and repair of the gate valve for the blow-off pipe. It is further recommended that the owners develop a periodic maintenance plan and operational procedures and prepare an emergency action plan and downstream warning system.


Abraham Perera P.E.
Project Manager



OVERVIEW OF EAST HIGHLAND LAKE DAM
MARCH, 1981

TABLE OF CONTENTS

	<u>Page</u>
Assessment of General Conditions	
Overall View of Dam	
Table of Contents	
Preface	
Section 1 - Project Information	1-5
Section 2 - Engineering Data	6-7
Section 3 - Visual Inspection	8-10
Section 4 - Operational Procedures	11
Section 5 - Hydraulic/Hydrologic	12
Section 6 - Structural Stability	13-14
Section 7 - Assessments/Recommendations/ Remedial Measures	15-16

FIGURES

- Figure 1 - Regional Vicinity Map
- Figure 2 - Plan of Dam
- Figure 3 - Spillway and Dam Sections

APPENDIX

Check List - Visual Inspection	i-viii
Check List - Engineering Data	ix-xii
Photographs	
Check List - Hydrologic and Hydraulic Data Computations	

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines can be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of Phase I investigations is to identify expeditiously those dams that may pose hazards to human life or property. The assessment of the general condition of the dam is based on available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In the review of this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway test flood is based on the estimated "probable maximum flood" for the region (greatest reasonable possible storm runoff) or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
NAME OF DAM: EAST HIGHLAND LAKE DAM FED ID# NJ 00288
AND NJ ID # 22-154

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL

a. Authority

This report is authorized by the Dam Inspection Act, Public Law 92-367, and has been prepared in accordance with Contract FPM-36 between Louis Berger & Associates, Inc. and the State of New Jersey and its Department of Environmental Protection, Division of Water Resources. The State, in turn, is under agreement with the U.S. Army Engineer District, Philadelphia to have this inspection performed.

b. Purpose of Inspection

The purpose of this inspection is to evaluate the structural and hydraulic condition of the East Highland Lake Dam and appurtenant structures and to determine if the dam constitutes a hazard to human life or property.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

East Highland Lake Dam is a 550-foot-long earth structure with a concrete spillway located at the left abutment. The embankment, which has a maximum height of 15 feet, is also 15 feet wide at the crest with 2H:1V side slopes. This three-zoned structure rests on bedrock at both abutments and has an impermeable, puddled-clay core and cutoff trench, a pervious earth downstream embankment, and an impervious clay-fill embankment upstream. The 30-foot-long spillway rests on bedrock and has a 5-foot-long, 0.4-foot-deep weir notch located in its center. The spillway outfall, which is constructed of grouted masonry paving, extends around the left end of the dam's toe to a natural stream channel about 175 feet from the left abutment. Concrete wingwalls extending along both sides of the outfall

to the toe of the dam channelize the discharge. A 60-foot-long concrete cutoff adjoins the spillway and extends from the crest of the dam down to bedrock. A 12-inch-diameter gate-operated steel pipe at invert elevation 100 functions as a low-level drain.

b. Location

The dam is located across a tributary to Warwick Creek at the north end of East Highland Lake in the community of Highland Lakes, Vernon Township, Sussex, New Jersey. It is 2 miles east of the intersection of County 515 and Breakneck Road and is centrally located between Highland Lake, Lake Wanda, and Wawayande Lake. The dam may be reached via a private driveway at the north end of West Lakeside Drive.

c. Size Classification

The dam at East Highland Lake has a maximum height of 15 feet and a maximum storage capacity of 244 acre-feet. Accordingly, this dam is in the small size category as defined by the criteria in the Recommended Guidelines for Safety Inspection of Dams (storage less than 1,000 acre-feet and height less than 40 feet).

d. Hazard Classification

The dam is located in a relatively populated residential lake community. The downstream valley is approximately 200 feet wide for about 800 feet below the dam, at which point the stream passes under a small local road and enters a very large, essentially uninhabited marsh. There are several homes located along the sides of the valley that are 6 to 8 feet above the small, shallow stream channel. There are also two occupied house trailers near the road that are about 6 feet above the stream. It is the opinion of the inspection team that while loss of life is not highly probable, any of the downstream structures could sustain extensive flood damage in the event of a dam failure. Accordingly, it is recommended that the dam be evaluated within the framework of the significant hazard category.

e. Ownership

This dam is owned by the Highland Lakes Country & Community Association Inc., Highland Lakes, New Jersey, 07422.

f. Purpose of Dam

The purpose of the dam is to impound a recreational lake.

g. Design and Construction History

The dam was designed in 1946 by Newell C. Harrison, P.E. for the Highland Lakes Association of Vernon Township. Construction began in October 1946 and was completed in February 1947. Construction modifications of the original design consisted of replacement of steel or concrete sheeting with an impermeable clay cutoff and a change in the configuration and location of the spillway due to the occurrence of bedrock at unanticipated elevations.

h. Normal Operating Procedures

There are presently no formal operating procedures. However, a full-time maintenance crew is employed by the Lake Association for groundskeeping and repair of community property.

1.3 PERTINENT DATA

a. Drainage Area

East Highland Lake Dam has a drainage area of 0.5 square miles, which consists of wooded hills and marshland.

b. Total spillway capacity at maximum pool elevation
(top of dam) - 481 cfs

c. Elevations (assumed datum)

Top of dam	- 115.0
Principal spillway crest	- 111.7
Streambed at centerline of dam	- 100.0

d. Reservoir

Length of maximum pool (top of dam)	- 3,025 feet
Length of recreation pool (principal spillway crest)	- 2,950 feet

e. Storage (acre-feet)

Top of dam	- 244
Recreation pool	- 160

f. Reservoir Surface (acres)

Top of dam - 29.6
Recreation pool - 26.6

g. Dam

Type - Earth embankment with a concrete,
narrow-crested weir for a primary
spillway

Length - 550 feet

Height - 15 feet

Top width - 15 feet

Side slopes - 2H:1V

Zoning - Three zone construction: impervious
puddled clay core; impervious rolled
clay fill in upstream embankment; and
pervious earth fill in downstream
embankment

Impervious blanket - None

Cutoff - Puddled clay cutoff trench beneath clay
core

Grout curtain - None

Corewall - Concrete corewall, 60 feet long,
adjoining spillway

h. Diversion and Regulating Tunnel

Type - None

i. Spillway

Type - Concrete weir with center notch

Weir length - 30 feet

Notch length - 5 feet

Notch depth - 0.4 feet

Gates - None

U/S Channel - Not applicable

D/S Channel - Grouted masonry spillway apron with concrete wingwalls extending to natural channel downstream of dam toe

J. Regulating Outlets

Lake level regulated by 12-inch-diameter steel pipe located about 80 feet from left abutment at exit invert elevation 100. Concrete valve chamber located on downstream slope of dam.

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

Details of the original 1946 design plans and the 1947 as-built drawings were available from the microfilm records of the State Bureau of Flood Plain Management. Additional hydrologic and hydraulic data were obtained from the dam application, review report, and correspondence between the state's reviewing engineer and the designer. The design conforms with currently accepted structural engineering standards, although the design storm, as determined by the Central Jersey runoff curve, was somewhat smaller than contemporary standards suggest.

2.2 CONSTRUCTION

Although details pertaining to the actual construction of the dam were not available, correspondence and construction inspection reports by the State's reviewing engineer indicate that several design modifications were made during the construction process in response to unanticipated site conditions encountered. The changes were incorporated into as-built drawings, which basically reflect the dam's present configuration. The dam is situated in a region underlain by the Pre-Cambrian age Byram gneiss, a dense, hard, and characteristically banded metamorphic granitoid. The reservoir occupies what was once a small, rock-bound swampy depression caused by glacial scouring. The thin overburden in this area consists primarily of recent alluvium overlying glacial till. During the initial stages of construction, a trench was excavated in the overburden and the puddled clay core was extended down to the bedrock, thus forming a continuous cutoff to bedrock, from one abutment to the other.

2.3 OPERATION

There is no information available pertaining to dam operation. However, since the sole purpose of the dam is the impoundment of a lake for recreational purposes, the spillway appears adequate to perform, unattended, the water level regulation function at the dam.

2.4 EVALUATION

a. Availability

Sufficient engineering data were obtained to assess the structural stability of the embankment. The foundation stability was evaluated within the framework of data provided on the plans, the construction specifications, and geotechnical references pertaining to the damsite.

b. Adequacy

The field inspection and review of the available engineering data indicate that the dam is of conservative design and is structurally sound and well built. It is believed that the data available are adequate to render this assessment without the necessity of gathering additional information.

c. Validity

The available engineering data indicate that the design concepts are contemporary and conservative in nature. The dam appears to have been constructed according to the specifications and configuration depicted on the revised plans.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of East Highland Lake Dam took place on March 24, 1981. At the time of the inspection, water was discharging through the weir notch at the spillway, which resulted in a tail-water at the low level drain outlet. Maintenance has apparently been neglected for many years, and while the overall condition of the spillway is generally good, the embankment is in fair to poor condition.

b. Dam

The dam crest and both slopes of the embankment are overgrown with trees, some of which are as large as 16 inches in diameter. A well traveled, sinuous footpath winds through the birch trees on the crest, giving the dam's alignment a somewhat irregular appearance. The riprap on the upstream slopes has been displaced at several locations, and in some areas where severe erosion has occurred, it is missing completely. Very severe erosion was observed in at least five locations on the upstream face of the dam. The erosion gullies, which extend from the dam crest to the lake edge, range from 7 to 15 feet wide and, in two locations, cut back into the embankment as far as the centerline of the crest. At one of these locations, a path is incised on the downstream face of the dam, further reducing the width of that portion of the crest which still remains at true design grade. The surface of the dam crest undulates slightly due to erosion and the foot traffic on the dam. Similarly, alignment of the upstream face is somewhat irregular due to surface and wave erosion. Since the spillway channel curves around the left end of the dam and continues some distance along the dam's toe, it was difficult to determine if there are seepage problems in that area. However, the remainder of the downstream slope of the dam appeared firm and dry with no signs of dampness anywhere in evidence except at the margins of the discharge channel. No signs of slouging or cracking were noted on the downstream slope of the embankment although several small rodent burrows were observed near the right abutment.

c. Appurtenant Structures

The concrete spillway at the left abutment is in a generally good condition although a light accumulation of debris, consisting of a tire and some wood, was noted at the weir. There is a light build-up of sediment at the left upstream side of the weir, but it is of no consequence since it does not interfere with the spillway hydraulics and bedrock is exposed immediately adjacent to both sides of the weir, obviating any concern over additional sediment loading on that structure. The weir has vertical bars exposed along the crest that, presumably, were designed to support a flashboard, although none is presently in place. The weir cap has a fresher appearance than the rest of the spillway, although all of the concrete was in fair to good condition. Some efflorescence and minor spalling were observed on the spillway's left side-wall, and at the downstream end of the spillway channel, the left wingwall exhibited a little more extensive concrete deterioration on its top surface. The spillway channel is constructed on bedrock that is very irregular and cluttered with angular boulders and some debris. Small trees are growing within the channel, primarily in accumulated silt along the left wall.

The outlet of the 12-inch-diameter drain pipe is almost completely blocked with silt and debris. While the concrete headwall appears in satisfactory condition, the top two courses of block at the valve chamber have been displaced several inches. The chamber has no manhole cover and the wheel has been broken off the valve stem, leaving only the stubs of the spokes radiating off the hub. The chamber contained a great deal of silt, leaves, and debris, and the valve itself appeared to be leaking.

d. Reservoir Area

The terrain surrounding the lake is modestly sloped and wooded with residential development on both the east and west shorelines. The south end of the lake is less heavily developed and swampy. Much of the shoreline is formed by well-defined bedrock outcrops and all homes surrounding the lake are several feet above dam crest elevation.

e. Downstream Channel

The area immediately downstream is a flat 200-foot-wide flood plain with stands of trees and secondary vegetation. The discharge is carried in a narrow meandering channel to a road culvert about 800 feet downstream. There are several homes and occupied trailers in the downstream area between the dam and the road. The elevations of the downstream structures are estimated to range between 6 and 8 feet above the stream channel. Downstream of the road, the channel enters a relatively large uninhabited marsh.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

There are no formal operating procedures presently in existence although the Lake Association employs a permanent maintenance crew in addition to seasonal part-time help. This staff is responsible for groundskeeping, preventive maintenance, lake operations, and repairs associated with the community property and several lakes owned by the association. However, present operations appear to be restricted by funding limitations.

4.2 MAINTENANCE OF DAM

While the primary responsibility of the maintenance staff centers around groundskeeping, their duties also extend to repair work within their capability. However, it appears that the dam has received little maintenance for several years (as indicated by the thick growth on the embankment and the severe erosion on the upstream face of the dam).

4.3 MAINTENANCE OF OPERATING FACILITIES

There does not appear to be a formal maintenance program associated with the operational components of the dam and all exhibit signs of neglect and require remedial action.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

There is no formal warning system in effect at this dam. While observant residents living near the dam could note conditions during heavy storms and notify local authorities, it was observed that the downstream homes are situated quite close to the channel and it is felt that a warning system is necessary to provide sufficient advance notice in case of a hazardous storm condition or dam failure.

4.5 EVALUATION OF OPERATIONAL ADEQUACY

The present operational procedures and community safeguards are deemed to be inadequate in view of the position of the dam and the downstream hazards. An overall community warning system should be developed along with a more intensive program of inspection and maintenance (see Section 7).

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data

Pursuant to the Recommended Guidelines for Safety Inspection of Dams, East Highland Lake Dam is a small size and significant hazard dam. Accordingly, the 100-year frequency storm was chosen as the design flood by the inspecting engineers. Inflow to the reservoir for the selected storm was computed utilizing precipitation data from Technical Paper 40 and Technical Memorandum NWS HYDRO-35 by the HEC-1 Dam Safety version computer program, which gave a peak inflow of 1,163 cfs. Routing this storm through the reservoir reduced the peak discharge to 321 cfs. Since the spillway capacity is 481 cfs, it can safely accommodate the 100-year storm and is therefore considered adequate.

b. Experience Data

There are no streamflow records available for this site, nor have records been kept regarding the dam's hydraulic performance since its construction.

c. Visual Observations

There are no indications of hydraulic problems at the dam although the spillway and channel contained scattered debris. Water was passing through the weir notch at the time of inspection and there was ample freeboard with no indications of recent extreme high water elevations at the dam. However, the low level drain appears inoperable at the present time.

d. Overtopping Potential

Employing the discharge and spillway capacities contained herein, overtopping would not occur in the event of the 100-year frequency design storm. There are no records or indications that the dam has ever been overtopped.

e. Drawdown

A 12-inch-diameter valve operated steel pipe is available for drawdown to elevation 101. The estimated time to drawdown is 11 days.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. While the dam appears structurally stable, several conditions were observed that could jeopardize the long-term integrity of the structure. The apparent lack of maintenance at the dam has resulted in extensive deterioration of the upstream slope; if not repaired, this could ultimately result in an embankment failure. Several large eroded areas on the upstream side of the embankment extend into the dam crest as far as the centerline of the dam. If the erosion in these areas continues unchecked, it will cut through the entire dam crest, breaching the dam since the concrete corewall does not extend the entire length of the dam. While the accumulation of debris in the spillway and its channel restricts the hydraulic capacity somewhat, it is not considered critical with respect to the structural integrity of the dam. Based on the stable condition of, and vegetation observed at, the left downstream toe of the embankment, high flows in the spillway flume and channel do not appear to pose a threat to that portion of the dam.

- b. Design and Construction Data

From the review of the contract plans for the initial construction, the design appears to be well engineered, reflects a conservative approach, and employs conventional analytical techniques. Based on the visual observations of the condition of the dam and its hydraulic capacity, it is believed that additional studies are not necessary under the purview of Public Law 92-367.

- c. Operating Records

While the dam appears to have performed satisfactorily since its construction, normal embankment maintenance and concrete repairs appear to have been completely neglected. There are no records available of operations, maintenance, or inspections since the original construction was completed.

- d. Post Construction Changes

There have been no apparent hydraulic modifications or major structural improvements since the dam's initial installation. However, a portion of the

weir cap appears to be of more recent construction, exhibiting a fresher surface than the rest of the concrete in the spillway.

e. Seismic Stability

East Highland Lake Dam is located in Seismic Zone 1 in which seismic activity is slight and the additional structural loading imparted thereby is generally insignificant. Experience indicates that earthen dams in Zone 1 that are stable under static loading conditions will maintain their structural integrity when subjected to the negligible dynamic loads imposed by the weak seismicity characteristic of this area. This dam is considered to be structurally stable under static loading conditions.

SECTION 7 - ASSESSMENTS/RECOMMENDATIONS/
REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety

Subject to the inherent limitations of the Phase I visual inspection, East Highland Lake Dam appears to be in fair overall condition and the spillway can accommodate the 100-year design flood. No serious detrimental conditions were observed to render a structurally inadequate assessment, but the long-term integrity of the dam remains questionable until the remedial measures described below are completed.

The dam embankment, while designed and constructed in a conservative manner, exhibits many years of neglect. Continued inattention to the severe erosion at the crest will ultimately result in a dam breach. Since there is a potential for downstream flood damage in the event of this dam's failure, it is recommended that the dam be evaluated within the framework of the significant hazard classification.

b. Adequacy of Information

The information available is considered adequate with respect to the analyses and evaluation of the operation and stability of this dam.

c. Urgency

The remedial actions described below should be undertaken in the near future with the exception of those recommendations pertaining to the embankment erosion, which should be performed immediately.

d. Necessity for Further Study

In view of the general condition of this dam and its spillway capacity, which is more than adequate to accommodate the design storm, additional studies within the purview of Public Law 92-367 are considered unnecessary.

7.2 RECOMMENDATIONS/REMEDIAL MEASURES


a. Recommendations


The eroded areas and displaced riprap on the upstream face of the dam exhibit the greatest potential for impending problems at the dam and should be corrected immediately. The eroded areas should be filled and compacted with suitable embankment material and the riprap repositioned or replaced to prevent a recurrence of the condition. In addition, the owner should undertake the following repairs in the near future:

1. Remove all trees and brush from the dam, re-fill and regrade the dam crest, and reestablish a firm grass cover over the entire embankment.
2. The debris should be removed from the spillway and downstream channel.
3. The blow-off gate valve should be repaired and tested, the manhole cover replaced, the displaced block at the top of the manhole repaired, and the debris therein removed.
4. The deteriorated concrete at the spillway should be repaired.
5. The drain pipe should be cleared of the accumulated silt and debris.

b. O&M Maintenance and Procedures

It is recommended that the association's existing maintenance program be expanded and a periodic maintenance plan and operational procedures be developed. It is further recommended that the owners prepare an emergency action plan and warning system to minimize the damage potential downstream in the event of a dam failure.






PLAN OF EAST HIGHLAND LAKE DAM


NOT TO SCALE

FIGURE 2



ELEVATION OF ABUTMENTS

NOT TO SCALE



SPILLWAY PROFILE

NOT TO SCALE

SPILLWAY DETAILS EAST HIGHLAND LAKE DAM

Check List
Visual Inspection
Phase 1

Name Dam East Highland Lake Dam County Sussex State NJ Coordinators NUDEP

Date(s) Inspection March 24, 1981 Weather Sunny Temperature 50°

Pool Elevation at Time of Inspection 111.7 A.D. Tailwater at Time of Inspection 99.7 A.D.

Inspection Personnel:

T. Chapter

A. Perera

No representative of owner present.

A. Perera Recorder

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None observed	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed	
SLOUGHING OR EROSION OF EMBANKMENT AND ADJUTMENT SLOPES	Severe erosion on upstream slope 35 feet left of spillway, 55 to 70 feet left of spillway, 145 to 152 feet left of spillway (erosion extends to center of crest here), and 200 to 210 feet left of spillway (erosion extends across crest almost reaching a path on the downstream slope).	Severe erosion on dam crest should be filled with compacted embankment.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Slightly irregular	Vertical alignment irregularity. Probably due to paths. Horizontal alignment irregular due to erosion, foot traffic, and tree over-growth. Crest should be regraded.
RIPRAP FAILURES	Riprap displaced in same areas as severe erosion.	Riprap should be replaced.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
Vegetable	Birch trees predominate , growing out of both u/s and d/s slopes and they are beginning to invade the crest.	Should be all cut and cleared, particularly on crest.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Grades smoothly one into another except for heavy footpath erosion behind right abutment (concrete spillway).	Eroded areas should be filled.
ANY NOTICEABLE SEEPAGE	None observed	
STAFF GAGE AND RECORDER	None	
DRAINS	None	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	N/A	
INTAKE STRUCTURE	None observed	
OUTLET STRUCTURE	12" diameter iron pipe with concrete headwall and cement block gate chamber. Outlet pipe almost completely blocked by debris and soil. Valve wheel broken off and valve is leaking. No cover on the manhole and debris around valve. Top two courses of block have shifted	
OUTLET CHANNEL	Rock outcrops just ahead (d/s) of spillway. Channel 15-20 feet wide covered with boulders, fallen trees, and some debris.	All components should be repaired, manhole cover should be replaced and the debris should be removed.
EMERGENCY GATE	None observed	

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Concrete spalling at left wall. Recently constructed weir cap.	Spalling and concrete deterioration should be repaired.
APPROACH CHANNEL	Debris (old tires and lumber), partly filled in (left half of weir).	Needs cleaning and removal of silt.
DISCHARGE CHANNEL	Debris and small trees in channel.	Should be cleared.
BRIDGE AND PIERS	None	
	v	

INSTRUMENTATION

VISUAL EXAMINATION MONUMENTATION/SURVEYS	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	None	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER		

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Rocky and frequently steep slopes. Area developed with houses, wooden docks, and beaches.	
SEDIMENTATION	None observed except near spillway.	Should be removed.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Covered with boulders and fallen trees.	
SLOPES	400 feet downstream from dam, channel widens into a 200-300 foot wide flood plain.	
APPROXIMATE NO. OF HOMES AND POPULATION	One abandoned home in dilapidated condition 10 feet above channel elevation. Two occupied homes downstream from the first one within 300 feet of the dam. 800 feet downstream the channel is obstructed by a culvert under a paved road. In case of flooding, all could be inundated due to the flatness of the terrain. Two trailers in the area of the road are located in the floodplain 6-8 feet above the channel bottom.	Homes and road could sustain flood damage in the event of dam failure.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	Available microfilm, NUDEP, 23 Prospect St., Trenton, NJ, 08625
REGIONAL VICINITY MAP	Available USGS Quadrangle, Wawayanda, NJ - NY
CONSTRUCTION HISTORY	Available microfilm NUDEP
TYPICAL SECTIONS OF DAM	Available microfilm NUDEP
HYDROLOGIC/HYDRAULIC DATA	Available microfilm NUDEP
OUTLETS - PLAN	Available NUDEP
- DETAILS	Not available
-CONSTRAINTS	" "
-DISCHARGE RATINGS	" "
RAINFALL/RESERVOIR RECORDS	" "

ITEM	REMARKS
SPILLWAY PLAN	Available NUDEP
SECTIONS	"
DETAILS	"
OPERATING EQUIPMENT PLANS & DETAILS	" "

x


ITEM	REMARKS
DESIGN REPORTS	Not Available
GEOLOGY REPORTS	"
DESIGN COMPUTATIONS	"
HYDROLOGY & HYDRAULICS	Available microfilm NJDEP
DAM STABILITY	Not Available
SEEPAGE STUDIES	"
MATERIALS INVESTIGATIONS	"
BORING RECORDS	"
LABORATORY	"
FIELD	"
POST-CONSTRUCTION SURVEYS OF DAM	"
BORROW SOURCES.	"

ITEM	REMARKS
MONITORING SYSTEMS	None
MODIFICATIONS	None
HIGH POOL RECORDS	Not available
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	" "
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	" " "
MAINTENANCE OPERATION RECORDS	" " "



March, 1981

Spillway & Dam Crest



March, 1981

Spillway Outlet Channel




March, 1981

Sedimentation At Left Wall Of Spillway



March, 1981

Debris At Right Wall Of Spillway



March, 1981

Manhole & Headwall For 12"Ø Outlet Pipe



March, 1981

Erosion On Dam Crest

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 0.5 square miles
ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 111.7 A.D. (160 acre feet)
ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): -
ELEVATION MAXIMUM DESIGN POOL: -
ELEVATION TOP DAM: 115 A.D. (244 acre feet)
CREST: Spillway

- a. Elevation 112.0
- b. Type Concrete weir with 5 ft. wide notch at elev. 111.7
- c. Width 24 inches
- d. Length 25 feet
- e. Location Spillover Center of spillway weir
- f. Number and Type of Gates None

OUTLET WORKS: _____

- a. Type 12-inch-diameter steel pipe
- b. Location 80 feet from left abutment
- c. Entrance inverts 111 A.D.
- d. Exit inverts 100 A.D.
- e. Emergency draindown facilities Same

HYDROMETEOROLOGICAL GAGES: None

- a. Type _____
- b. Location _____
- c. Records _____

MAXIMUM NON-DAMAGING DISCHARGE: 481 cfs

A.D. - Assumed Datum

BY _____ DATE _____
CHKD. BY _____ DATE _____
SUBJECT _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A OF 1
PROJECT _____

1. - stream channel; All inflow overland

Length of overland flow = 3,400 ft.

$$L_n = 120 \text{ ft.} \quad \text{Slope} = \frac{120 \text{ ft.}}{3,400 \text{ ft.}} = 3.5 \%$$

$$\text{Assume overland velocity of 2 fps} \therefore t_1 = \frac{3,400}{2 \times 5,280} = 0.47 \text{ hr.}$$

2. - Culvert Culvert Methodology

$$T_2 = \left(\frac{11.9 \times .04^3}{120} \right)^{0.385} = 0.25 \text{ hr.}$$

3. - SCS Methodology

Gloucester soils - Group B

50% wooded ($C_n = 65$); 35% meadow ($C_n = 55$);

15% low density residential ($C_n = 45$).

Adjusted $C_n = 58$

Slope = 3.5%

$L = 3,400 \text{ ft.}$

$$L_{adj} = \frac{L^{0.8} (5-1)^{0.7}}{(120)^{0.7}} = \frac{3,400^{0.8} \times (4)^{0.7}}{(120)^{0.7}} = 0.52 \text{ hr.}$$

$$T_3 = L_{adj} = 0.52 \text{ hr.}$$

$$T_4 = T_1 + T_2 + T_3 = 0.47 + 0.25 + 0.52 = 1.24 \text{ hr.}$$

$$T_5 = 0.1 + 0.12 = 0.22 / 2 + 0.12 (0.22) = 0.25 \text{ hr.}$$

$$L_{adj} = L = 3,400 \text{ ft.} = 0.52 \text{ hr.}$$

BY _____ DATE JUL 1971
CHKD. BY _____ DATE _____
SUBJECT UNIT 3100

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 15 OF 41
PROJECT 65075

$A = 0.5 \text{ SEC. MIN.}$
 $LAG = 0.42 \text{ HRS}$

UNIT 3100 IS DEVELOPED BY THE HEC 1 DB
COMPUTER PROGRAM (V12 CASE)

BY _____ DATE 4/11/51
 CHKD. BY _____ DATE _____
 SUBJECT _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO 12 OF 13
 PROJECT CS 356
Test Storm: 100 Year Freq. 11/11/51

Precipitation data from TP-40 & NOAA Technical
 Memorandum NMIS Hydro - 35

Time	Precip.	Δ	RA	Time	Precip.	Δ	RA
0.1	.91	.91	.03	3.1	4.30	.05	.91
0.2	1.46	.55	.03	3.2	4.34	.04	.35
0.3	1.81	.35	.03	3.3	4.38	.04	.23
0.4	2.07	.26	.03	3.4	4.41	.03	.17
0.5	2.30	.23	.02	3.5	4.45	.04	.12
0.6	2.46	.16	.03	3.6	4.48	.03	.10
0.7	2.63	.17	.02	3.7	4.52	.04	.09
0.8	2.77	.14	.04	3.8	4.56	.04	.08
0.9	2.89	.12	.03	3.9	4.60	.04	.07
1.0	3.00	.11	.03	4.0	4.63	.03	.06
1.1	3.10	.10	.03	4.1	4.66	.03	.06
1.2	3.20	.10	.04	4.2	4.69	.03	.05
1.3	3.29	.09	.03	4.3	4.72	.03	.05
1.4	3.36	.07	.03	4.4	4.75	.03	.05
1.5	3.44	.08	.04	4.5	4.78	.03	.04
1.6	3.51	.07	.04	4.6	4.82	.04	.05
1.7	3.58	.07	.05	4.7	4.85	.03	.04
1.8	3.65	.07	.05	4.8	4.87	.02	.04
1.9	3.71	.06	.05	4.9	4.90	.03	.04
2.0	3.76	.05	.05	5.0	4.93	.03	.04
2.1	3.82	.06	.05	5.1	4.96	.03	.03
2.2	3.87	.05	.07	5.2	4.98	.02	.03
2.3	3.92	.05	.07	5.3	5.01	.03	.03
2.4	3.97	.05	.07	5.4	5.04	.03	.03
2.5	4.02	.05	.10	5.5	5.06	.02	.03
2.6	4.07	.05	.11	5.6	5.09	.03	.03
2.7	4.12	.05	.14	5.7	5.12	.03	.03
2.8	4.17	.05	.16	5.8	5.15	.03	.02
2.9	4.21	.04	.26	5.9	5.17	.02	.03
3.0	4.25	.04	.55	6.0	5.20	.03	.02

BY _____ DATE May 1961

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 1 OF 1

CHKD. BY _____ DATE _____

East Highland Lake Dam

PROJECT 5000

SUBJECT _____

Stage Discharge

Flow Over
Spilling Notch
L = 5' EL. = 111.5.7"

Flow Over
Spilling Crest
L = 25' EL. = 112.5"


Over Dam
L = 515'
EL. = 113"

H	C	Q	H	C	Q	H	C	Q	Σ Q
0.33	3.0	3	0	3.0				2.7	3
1.33		23	1		75				98
2.33		58	2		212				265
3.33		91	3		390	0			481
4.33		135	4		600	1	1,391		2,126
5.33		180	5		829	2	3,930		4,451
6.33		239	6		1,102	3	7,225		8,566
7.33		298	7		1,389	4	11,124		12,911
8.33		367	8		1,697	5	15,546		17,644
9.33		427	9		2,025	6	20,416		22,869

* Actual stage

A5 of A13

EAST HIGHLAND LAKE DAM STAGE - DISCHARGE CURVE



BY _____ DATE July 31
 CHK'D. BY _____ DATE _____
 SUBJECT _____


LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 42 OF 100
 PROJECT W. 122

Area of lot at normal pool elev. 11.17 = 26.6 ac.
 Area of 1230' contour (A - 11.17) = 36.7 ac.

Ex. 2 Storage Volume = 44,000 cu. yd.

W. 122




Ex. 11.17

Elev.	Ht. above spring (dy)	(x 27.00) (cu. yd.)	Storage (cu. yd.)
11.17	0		
11.27	1	27.0	27
11.37	2	54.0	54
11.47	3	81.0	81
11.57	4	108.0	108
11.67	5	135.0	135
11.77	6	162.0	162
11.87	7	189.0	189
11.97	8	216.0	216
12.07	9	243.0	243
12.17	10	270.0	270
12.27	11	297.0	297
12.37	12	324.0	324
12.47	13	351.0	351
12.57	14	378.0	378
12.67	15	405.0	405
12.77	16	432.0	432
12.87	17	459.0	459
12.97	18	486.0	486
13.07	19	513.0	513
13.17	20	540.0	540
13.27	21	567.0	567
13.37	22	594.0	594
13.47	23	621.0	621
13.57	24	648.0	648
13.67	25	675.0	675
13.77	26	702.0	702
13.87	27	729.0	729
13.97	28	756.0	756
14.07	29	783.0	783
14.17	30	810.0	810
14.27	31	837.0	837
14.37	32	864.0	864
14.47	33	891.0	891
14.57	34	918.0	918
14.67	35	945.0	945
14.77	36	972.0	972
14.87	37	999.0	999
14.97	38	1026.0	1026
15.07	39	1053.0	1053
15.17	40	1080.0	1080
15.27	41	1107.0	1107
15.37	42	1134.0	1134
15.47	43	1161.0	1161
15.57	44	1188.0	1188
15.67	45	1215.0	1215
15.77	46	1242.0	1242
15.87	47	1269.0	1269
15.97	48	1296.0	1296
16.07	49	1323.0	1323
16.17	50	1350.0	1350
16.27	51	1377.0	1377
16.37	52	1404.0	1404
16.47	53	1431.0	1431
16.57	54	1458.0	1458
16.67	55	1485.0	1485
16.77	56	1512.0	1512
16.87	57	1539.0	1539
16.97	58	1566.0	1566
17.07	59	1593.0	1593
17.17	60	1620.0	1620
17.27	61	1647.0	1647
17.37	62	1674.0	1674
17.47	63	1701.0	1701
17.57	64	1728.0	1728
17.67	65	1755.0	1755
17.77	66	1782.0	1782
17.87	67	1809.0	1809
17.97	68	1836.0	1836
18.07	69	1863.0	1863
18.17	70	1890.0	1890
18.27	71	1917.0	1917
18.37	72	1944.0	1944
18.47	73	1971.0	1971
18.57	74	1998.0	1998
18.67	75	2025.0	2025
18.77	76	2052.0	2052
18.87	77	2079.0	2079
18.97	78	2106.0	2106
19.07	79	2133.0	2133
19.17	80	2160.0	2160
19.27	81	2187.0	2187
19.37	82	2214.0	2214
19.47	83	2241.0	2241
19.57	84	2268.0	2268
19.67	85	2295.0	2295
19.77	86	2322.0	2322
19.87	87	2349.0	2349
19.97	88	2376.0	2376
20.07	89	2403.0	2403
20.17	90	2430.0	2430
20.27	91	2457.0	2457
20.37	92	2484.0	2484
20.47	93	2511.0	2511
20.57	94	2538.0	2538
20.67	95	2565.0	2565
20.77	96	2592.0	2592
20.87	97	2619.0	2619
20.97	98	2646.0	2646
21.07	99	2673.0	2673
21.17	100	2700.0	2700
21.27	101	2727.0	2727
21.37	102	2754.0	2754
21.47	103	2781.0	2781
21.57	104	2808.0	2808
21.67	105	2835.0	2835
21.77	106	2862.0	2862
21.87	107	2889.0	2889
21.97	108	2916.0	2916
22.07	109	2943.0	2943
22.17	110	2970.0	2970
22.27	111	2997.0	2997
22.37	112	3024.0	3024
22.47	113	3051.0	3051
22.57	114	3078.0	3078
22.67	115	3105.0	3105
22.77	116	3132.0	3132
22.87	117	3159.0	3159
22.97	118	3186.0	3186
23.07	119	3213.0	3213
23.17	120	3240.0	3240
23.27	121	3267.0	3267
23.37	122	3294.0	3294
23.47	123	3321.0	3321
23.57	124	3348.0	3348
23.67	125	3375.0	3375
23.77	126	3402.0	3402
23.87	127	3429.0	3429
23.97	128	3456.0	3456
24.07	129	3483.0	3483
24.17	130	3510.0	3510
24.27	131	3537.0	3537
24.37	132	3564.0	3564
24.47	133	3591.0	3591
24.57	134	3618.0	3618
24.67	135	3645.0	3645
24.77	136	3672.0	3672
24.87	137	3699.0	3699
24.97	138	3726.0	3726
25.07	139	3753.0	3753
25.17	140	3780.0	3780
25.27	141	3807.0	3807
25.37	142	3834.0	3834
25.47	143	3861.0	3861
25.57	144	3888.0	3888
25.67	145	3915.0	3915
25.77	146	3942.0	3942
25.87	147	3969.0	3969
25.97	148	3996.0	3996
26.07	149	4023.0	4023
26.17	150	4050.0	4050
26.27	151	4077.0	4077
26.37	152	4104.0	4104
26.47	153	4131.0	4131
26.57	154	4158.0	4158
26.67	155	4185.0	4185
26.77	156	4212.0	4212
26.87	157	4239.0	4239
26.97	158	4266.0	4266
27.07	159	4293.0	4293
27.17	160	4320.0	4320
27.27	161	4347.0	4347
27.37	162	4374.0	4374
27.47	163	4401.0	4401
27.57	164	4428.0	4428
27.67	165	4455.0	4455
27.77	166	4482.0	4482
27.87	167	4509.0	4509
27.97	168	4536.0	4536
28.07	169	4563.0	4563
28.17	170	4590.0	4590
28.27	171	4617.0	4617
28.37	172	4644.0	4644
28.47	173	4671.0	4671
28.57	174	4698.0	4698
28.67	175	4725.0	4725
28.77	176	4752.0	4752
28.87	177	4779.0	4779
28.97	178	4806.0	4806
29.07	179	4833.0	4833
29.17	180	4860.0	4860
29.27	181	4887.0	4887
29.37	182	4914.0	4914
29.47	183	4941.0	4941
29.57	184	4968.0	4968
29.67	185	4995.0	4995
29.77	186	5022.0	5022
29.87	187	5049.0	5049
29.97	188	5076.0	5076
30.07	189	5103.0	5103
30.17	190	5130.0	5130
30.27	191	5157.0	5157
30.37	192	5184.0	5184
30.47	193	5211.0	5211
30.57	194	5238.0	5238
30.67	195	5265.0	5265
30.77	196	5292.0	5292
30.87	197	5319.0	5319
30.97	198	5346.0	5346
31.07	199	5373.0	5373
31.17	200	5400.0	5400
31.27	201	5427.0	5427
31.37	202	5454.0	5454
31.47	203	5481.0	5481
31.57	204	5508.0	5508
31.67	205	5535.0	5535
31.77	206	5562.0	5562
31.87	207	5589.0	5589
31.97	208	5616.0	5616
32.07	209	5643.0	5643
32.17	210	5670.0	5670
32.27	211	5697.0	5697
32.37	212	5724.0	5724
32.47	213	5751.0	5751
32.57	214	5778.0	5778
32.67	215	5805.0	5805
32.77	216	5832.0	5832
32.87	217	5859.0	5859
32.97	218	5886.0	5886
33.07	219	5913.0	5913
33.17	220	5940.0	5940
33.27	221	5967.0	5967
33.37	222	5994.0	5994
33.47	223	6021.0	6021
33.57	224	6048.0	6048
33.67	225	6075.0	6075
33.77	226	6102.0	6102
33.87	227	6129.0	6129
33.97	228	6156.0	6156
34.07	229	6183.0	6183
34.17	230	6210.0	6210
34.27	231	6237.0	6237
34.37	232	6264.0	6264
34.47	233	6291.0	6291
34.57	234	6318.0	6318
34.67	235	6345.0	6345
34.77	236	6372.0	6372
34.87	237	6399.0	6399
34.97	238	6426.0	6426
35.07	239	6453.0	6453
35.17	240	6480.0	6480
35.27	241	6507.0	6507
35.37	242	6534.0	6534
35.47	243	6561.0	6561
35.57	244	6588.0	6588
35.67	245	6615.0	6615
35.77	246	6642.0	6642
35.87	247	6669.0	6669
35.97	248	6696.0	6696
36.07	249	6723.0	6723
36.17	250	6750.0	6750
36.27	251	6777.0	6777
36.37	252	6804.0	6804
36.47	253	6831.0	6831
36.57	254	6858.0	6858
36.67	255	6885.0	6885
36.77	256	6912.0	6912
36.87	257	6939.0	6939
36.97	258	6966.0	6966
37.07	259	6993.0	6993
37.17	260	7020.0	7020
37.27	261	7047.0	7047
37.37	262	7074.0	7074
37.47	263	7101.0	7101
37.57	264	7128.0	7128
37.67	265	7155.0	7155
37.77	266	7182.0	7182
37.87	267	7209.0	7209
37.97	268	7236.0	7236
38.07	269	7263.0	7263
38.17	270	729	

AS - A12

EAST HIGHLAND LAKE DAM
STAGE-DISCHARGE STORAGE
CURVE



STAGE IN FEET - DISCHARGE IN CFS

BY: _____ DATE: June 21

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A-1 OF 112

CHKD. BY: _____ DATE: _____

PROJECT: CF

SUBJECT: _____

Summary for H&B Report

<u>H&B Above</u>	<u>Storage</u>	<u>H&B Below</u>	<u>Line 2 of 2</u>
<u>Spill 2.25</u>	<u>100.00</u>	<u>100.00</u>	<u>100.00</u>
1	27	1.33	3
2	58	1.33	28
3	84	2.33	235
4	114	3.33	28
5	145	4.33	211
6	177	5.33	4,957
7	210	6.33	3,021
8	241	7.33	10
9	279	8.33	17,604
10	315	9.33	21.5

Top of
Bain →

BY _____ DATE 7/1/68

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. A-1 OF 10

CHKD. BY _____ DATE _____

Ed. H. and J. S.

PROJECT WINDS

SUBJECT _____

Winds in Lake

Length of the 12" steel pipe

normal pipe diameter = 112 (1000 1210)

normal pipe diameter = 101

Order from steel mill = 100

Total length to top of pipe at outlet = 110 ft.

Assume inflow at 2.5 ft. inflow = 0.5 cfs

From data app. 10 ft.

10 ft. of pipe = 10 ft. of pipe (100 ft. of pipe)

$C = 0.01 \sqrt{2.5}$

$C = 0.02$

$A = 0.79 \text{ ft}^2$

$H_{avg} = 5.5 \text{ ft}$

$C = 0.02, 0.79, 5.5$

$C = 7.7 \times 10 = 0.5 \text{ cfs} = 7.2 \text{ cfs}$

Time = $\frac{100 \times 5.5 \times 2.5}{7.2 \times 2.556} = 2.0 \text{ sec}$

11.2 days

BY DATE

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 112 OF 117

CHKD. BY DATE

PROJECT

SUBJECT

A1 EAST HIGHLAND LAKE DAM HEC-1 DB

A2 J. CERAVOLO

A3 JUNE 19 1981

B 100 0 6 0 0 0 0 0 0 0

B1 3

K 0 1

K1 INFLOW HYDROGRAPH TO RESERVOIR

M 0 2 0.5 0

D 60

O1 .03 .03 .03 .03 .02 .03 .02 .04 .03 .03

O1 .03 .04 .03 .03 .04 .04 .05 .05 .05 .05

O1 .05 .07 .07 .07 .10 .11 .14 .16 .26 .55

O1 .91 .35 .23 .17 .12 .10 .09 .05 .07 .06

O1 .06 .05 .05 .05 .04 .05 .04 .04 .04 .04

O1 .03 .03 .03 .03 .03 .03 .03 .02 .03 .02

T 0.5 0.1

W2 0.42

X 0 0 1

K 1 2 1

K1 ROUTED FLOWS THROUGH RESERVOIR

Y 1 1

Y1 1 112 113 114 115 116 117 118 119 120

Y5 0 3 98 265 481 2126 4957 8566 12811 17604

S 0 27.1 55.2 84.3 114.4 145.5 177.6 210.7 244.8

SE 111.7 112.7 113.7 114.7 115.7 116.7 117.7 118.7 119.7

SS 111.7

SD 115

K 99

JOB SPECIFICATION

NQ 100 NHR 0 NMIN 6 IDAY 0 IHR 0 IMIN 0 METRC 0 IPLT 0 IPRT 0 NSTAN 0

JOPER 3 NWT 0 LROPT 0 TRACE 0

INFLOW HYDROGRAPH TO RESERVOIR

ISTAG 1 ICOMP 0 IECON 0 ITAPE 0 JPLT 0 JPRT 0 INAME 1 ISTAGE 0 IAUTO 0

HYDROGRAPH DATA

IHYD 0 IUHG 2 TAREA 0.50 SNAP 0.00 TRSDA 0.50 TRSPC 0.00 RATIO 0.000 ISNOW 0 ISAME 0 LOCAL 0

PRECIP PATTERN

0.03	0.03	0.03	0.03	0.02	0.03	0.02	0.04	0.03	0.03
0.03	0.04	0.03	0.03	0.04	0.04	0.05	0.05	0.05	0.05
0.03	0.07	0.07	0.07	0.10	0.11	0.14	0.16	0.26	0.55
0.91	0.35	0.23	0.17	0.12	0.10	0.09	0.08	0.07	0.06
0.06	0.05	0.05	0.05	0.04	0.05	0.04	0.04	0.04	0.04
0.03	0.03	0.03	0.03	0.03	0.03	0.03	0.02	0.03	0.02

LOSS DATA

LROPT 0 STRKR 0.00 DLTGR 0.00 RTIOL 1.00 ERAIN 0.00 STRKS 0.00 RTIOK 1.00 STRTL 0.50 CNSTL 0.10 ALSMX 0.00 RTIMP 0.00

UNIT HYDROGRAPH DATA

SUB-AREA RUNOFF COMPUTATION

PRECIP DATA

NP 60 STORM 0.00 DAJ 0.00 DAK 0.00
TC= 0.00 LAG= 0.42

RECESSION DATA

STRIG= 0.00 GRCEN= 0.00 RTIOR= 1.00

UNIT HYDROGRAPH END OF PERIOD ORDINATES, TC= 0.00 HOURS, LAG= 0.42 VOL= 1.00

57	1.0	371	494	511	451	355	236	166	120
05	6.0	42	29	21	15	11	7	5	4
3	2	1							

PEAK 2-HOUR 24-HOUR 72-HOUR TOTAL VOLUME

HYDROGRAPH ROUTING

NSTPS 1 NSTDI 0 LAG 0 AMEAK 0 X 0 TSK 0 STORA 0 ISPRAT -1

BY _____ DATE _____
CHKD. BY _____ DATE _____
SUBJECT _____

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 1 OF 1
PROJECT _____

END-OF-PERIOD FLOW										PERIOD				RAIN				EXCS				LOSS				COMP. Q			
MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q	MO. DA	HR. MN	PERIOD	RAIN	EXCS	LOSS	COMP. Q		
1 01	0 04	1	0.03	0.00	0.03	0	1 01	5 06	51	0.03	0.02	0.01	0.01	1 01	5 06	51	0.03	0.02	0.01	0.01	1 01	5 06	51	0.03	0.02	0.01	0.01		
1 01	0 12	2	0.03	0.00	0.03	0	1 01	5 12	52	0.03	0.02	0.01	0.01	1 01	5 12	52	0.03	0.02	0.01	0.01	1 01	5 12	52	0.03	0.02	0.01	0.01		
1 01	0 24	3	0.03	0.00	0.03	0	1 01	5 19	53	0.03	0.02	0.01	0.01	1 01	5 24	54	0.03	0.02	0.01	0.01	1 01	5 24	54	0.03	0.02	0.01	0.01		
1 01	0 36	4	0.02	0.00	0.02	0	1 01	5 30	55	0.03	0.02	0.01	0.01	1 01	5 30	55	0.03	0.02	0.01	0.01	1 01	5 30	55	0.03	0.02	0.01	0.01		
1 01	0 48	5	0.03	0.00	0.03	0	1 01	5 36	56	0.03	0.02	0.01	0.01	1 01	5 42	57	0.03	0.02	0.01	0.01	1 01	5 42	57	0.03	0.02	0.01	0.01		
1 01	0 59	6	0.02	0.00	0.02	0	1 01	5 48	58	0.02	0.01	0.01	0.01	1 01	5 48	59	0.02	0.01	0.01	0.01	1 01	5 48	59	0.02	0.01	0.01	0.01		
1 01	1 09	7	0.03	0.00	0.03	0	1 01	5 54	59	0.03	0.02	0.01	0.01	1 01	6 00	60	0.03	0.02	0.01	0.01	1 01	6 00	60	0.03	0.02	0.01	0.01		
1 01	1 20	8	0.03	0.00	0.03	0	1 01	6 06	61	0.03	0.02	0.01	0.01	1 01	6 06	61	0.03	0.02	0.01	0.01	1 01	6 06	61	0.03	0.02	0.01	0.01		
1 01	1 31	9	0.03	0.00	0.03	0	1 01	6 12	62	0.03	0.02	0.01	0.01	1 01	6 12	62	0.03	0.02	0.01	0.01	1 01	6 12	62	0.03	0.02	0.01	0.01		
1 01	1 42	10	0.03	0.00	0.03	0	1 01	6 13	63	0.03	0.02	0.01	0.01	1 01	6 13	63	0.03	0.02	0.01	0.01	1 01	6 13	63	0.03	0.02	0.01	0.01		
1 01	1 53	11	0.03	0.00	0.03	0	1 01	6 24	64	0.03	0.02	0.01	0.01	1 01	6 24	64	0.03	0.02	0.01	0.01	1 01	6 24	64	0.03	0.02	0.01	0.01		
1 01	2 04	12	0.04	0.00	0.04	0	1 01	6 30	65	0.04	0.03	0.01	0.01	1 01	6 30	65	0.04	0.03	0.01	0.01	1 01	6 30	65	0.04	0.03	0.01	0.01		
1 01	2 15	13	0.04	0.00	0.04	0	1 01	6 36	66	0.04	0.03	0.01	0.01	1 01	6 36	66	0.04	0.03	0.01	0.01	1 01	6 36	66	0.04	0.03	0.01	0.01		
1 01	2 26	14	0.05	0.00	0.05	0	1 01	6 42	67	0.05	0.04	0.01	0.01	1 01	6 42	67	0.05	0.04	0.01	0.01	1 01	6 42	67	0.05	0.04	0.01	0.01		
1 01	2 37	15	0.05	0.00	0.05	0	1 01	6 48	68	0.05	0.04	0.01	0.01	1 01	6 48	68	0.05	0.04	0.01	0.01	1 01	6 48	68	0.05	0.04	0.01	0.01		
1 01	2 48	16	0.05	0.00	0.05	0	1 01	6 54	69	0.05	0.04	0.01	0.01	1 01	6 54	69	0.05	0.04	0.01	0.01	1 01	6 54	69	0.05	0.04	0.01	0.01		
1 01	2 59	17	0.05	0.00	0.05	0	1 01	7 00	70	0.05	0.04	0.01	0.01	1 01	7 00	70	0.05	0.04	0.01	0.01	1 01	7 00	70	0.05	0.04	0.01	0.01		
1 01	3 10	18	0.07	0.00	0.07	0	1 01	7 06	71	0.07	0.06	0.01	0.01	1 01	7 06	71	0.07	0.06	0.01	0.01	1 01	7 06	71	0.07	0.06	0.01	0.01		
1 01	3 21	19	0.07	0.00	0.07	0	1 01	7 12	72	0.07	0.06	0.01	0.01	1 01	7 12	72	0.07	0.06	0.01	0.01	1 01	7 12	72	0.07	0.06	0.01	0.01		
1 01	3 32	20	0.07	0.00	0.07	0	1 01	7 18	73	0.07	0.06	0.01	0.01	1 01	7 18	73	0.07	0.06	0.01	0.01	1 01	7 18	73	0.07	0.06	0.01	0.01		
1 01	3 43	21	0.10	0.00	0.10	0	1 01	7 24	74	0.10	0.07	0.01	0.01	1 01	7 24	74	0.10	0.07	0.01	0.01	1 01	7 24	74	0.10	0.07	0.01	0.01		
1 01	3 54	22	0.10	0.00	0.10	0	1 01	7 30	75	0.10	0.07	0.01	0.01	1 01	7 30	75	0.10	0.07	0.01	0.01	1 01	7 30	75	0.10	0.07	0.01	0.01		
1 01	4 05	23	0.12	0.00	0.12	0	1 01	7 36	76	0.12	0.08	0.01	0.01	1 01	7 36	76	0.12	0.08	0.01	0.01	1 01	7 36	76	0.12	0.08	0.01	0.01		
1 01	4 16	24	0.15	0.00	0.15	0	1 01	7 42	77	0.15	0.09	0.01	0.01	1 01	7 42	77	0.15	0.09	0.01	0.01	1 01	7 42	77	0.15	0.09	0.01	0.01		
1 01	4 27	25	0.25	0.00	0.25	0	1 01	7 48	78	0.25	0.15	0.01	0.01	1 01	7 48	78	0.25	0.15	0.01	0.01	1 01	7 48	78	0.25	0.15	0.01	0.01		
1 01	4 38	26	0.35	0.00	0.35	0	1 01	7 54	79	0.35	0.25	0.01	0.01	1 01	7 54	79	0.35	0.25	0.01	0.01	1 01	7 54	79	0.35	0.25	0.01	0.01		
1 01	4 49	27	0.55	0.00	0.55	0	1 01	8 00	80	0.55	0.34	0.01	0.01	1 01	8 00	80	0.55	0.34	0.01	0.01	1 01	8 00	80	0.55	0.34	0.01	0.01		
1 01	5 00	28	0.91	0.00	0.91	0	1 01	8 06	81	0.91	0.54	0.01	0.01	1 01	8 06	81	0.91	0.54	0.01	0.01	1 01	8 06	81	0.91	0.54	0.01	0.01		
1 01	5 11	29	0.35	0.00	0.35	0	1 01	8 12	82	0.35	0.23	0.01	0.01	1 01	8 12	82	0.35	0.23	0.01	0.01	1 01	8 12	82	0.35	0.23	0.01	0.01		
1 01	5 22	30	0.17	0.00	0.17	0	1 01	8 18	83	0.17	0.10	0.01	0.01	1 01	8 18	83	0.17	0.10	0.01	0.01	1 01	8 18	83	0.17	0.10	0.01	0.01		
1 01	5 33	31	0.12	0.00	0.12	0	1 01	8 24	84	0.12	0.11	0.01	0.01	1 01	8 24	84	0.12	0.11	0.01	0.01	1 01	8 24	84	0.12	0.11	0.01	0.01		
1 01	5 44	32	0.09	0.00	0.09	0	1 01	8 30	85	0.09	0.09	0.01	0.01	1 01	8 30	85	0.09	0.09	0.01	0.01	1 01	8 30	85	0.09	0.09	0.01	0.01		
1 01	5 55	33	0.03	0.00	0.03	0	1 01	8 36	86	0.03	0.07	0.01	0.01	1 01	8 36	86	0.03	0.07	0.01	0.01	1 01	8 36	86	0.03	0.07	0.01	0.01		
1 01	6 06	34	0.06	0.00	0.06	0	1 01	8 42	87	0.06	0.05	0.01	0.01	1 01	8 42	87	0.06	0.05	0.01	0.01	1 01	8 42	87	0.06	0.05	0.01	0.01		
1 01	6 17	35	0.06	0.00	0.06	0	1 01	8 48	88	0.06	0.05	0.01	0.01	1 01	8 48	88	0.06	0.05	0.01	0.01	1 01	8 48	88	0.06	0.05	0.01	0.01		
1 01	6 28	36	0.06	0.00	0.06	0	1 01	8 54	89	0.06	0.05	0.01	0.01	1 01	8 54	89	0.06	0.05	0.01	0.01	1 01	8 54	89	0.06	0.05	0.01	0.01		
1 01	6 39	37	0.06	0.00	0.06	0	1 01	9 00	90	0.06	0.05	0.01	0.01	1 01	9 00	90	0.06	0.05	0.01	0.01	1 01	9 00	90	0.06	0.05	0.01	0.01		
1 01	6 50	38	0.06	0.00	0.06	0	1 01	9 06	91	0.06	0.05	0.01	0.01	1 01	9 06	91	0.06	0.05	0.01	0.01	1 01	9 06	91	0.06	0.05	0.01	0.01		
1 01	7 01	39	0.05	0.00	0.05	0	1 01	9 12	92	0.05	0.04	0.01	0.01	1 01	9 12	92	0.05	0.04	0.01	0.01	1 01	9 12	92	0.05	0.04	0.01	0.01		
1 01	7 12	40	0.05	0.00	0.05	0	1 01	9 18	93	0.05	0.04	0.01	0.01	1 01	9 18	93	0.05	0.04	0.01	0.01	1 01	9 18	93	0.05	0.04	0.01	0.01		
1 01	7 23	41	0.05	0.00	0.05	0	1 01	9 24	94	0.05	0.04	0.01	0.01	1 01	9 24	94	0.05	0.04	0.01	0.01	1 01	9 24	94	0.05	0.04	0.01	0.01		
1 01	7 34	42	0.04	0.00	0.04	0	1 01	9 30	95	0.04	0.03	0.01	0.01	1 01	9 30	95	0.04	0.03	0.01	0.01	1 01	9 30	95	0.04	0.03	0.01	0.01		
1 01	7 45	43	0.04	0.00	0.04	0	1 01	9 36	96	0.04																			

SHEET NO. 12 OF 12
PROJECT: 6-2112

	END-OF-PERIOD HYDROGRAPH COORDINATES					
MO DA	HR. MIN	PERIOD HOURS	INFLOW	OUTFLOW	STORAGE	STAGE
1	01	0.06	1	0.10	0.	111.7

[illegible]

BY: LC DATE: 3/1/76

LOUIS BERGER & ASSOCIATES INC.

SHEET NO. 1 OF 2

CHKD. BY: DATE

PROJECT: 276

SUBJECT: 175-12-2

1.01	6.24	64	6.40	35	175	49	113.5
1.01	6.30	65	6.50	26	168	47	113.4
1.01	6.35	66	6.60	18	161	46	113.4
1.01	6.42	67	6.70	13	154	45	113.3
1.01	6.48	68	6.80	9	148	44	113.3
1.01	6.54	69	6.90	6	141	43	113.3
1.01	7.00	70	7.00	4	134	42	113.2
1.01	7.06	71	7.10	3	128	41	113.2
1.01	7.12	72	7.20	2	122	40	113.1
1.01	7.18	73	7.30	2	116	39	113.1
1.01	7.24	74	7.40	1	111	39	113.1
1.01	7.30	75	7.50	1	105	37	113.0
1.01	7.36	76	7.60	0	100	36	113.0
1.01	7.42	77	7.70	0	97	35	113.0
1.01	7.48	78	7.80	0	94	34	113.0
1.01	7.54	79	7.90	0	91	34	112.9
1.01	8.00	80	8.00	0	89	33	112.9
1.01	8.06	81	8.10	0	86	32	112.9
1.01	8.12	82	8.20	0	84	31	112.9
1.01	8.18	83	8.30	0	82	31	112.8
1.01	8.24	84	8.40	0	80	30	112.8
1.01	8.30	85	8.50	0	77	29	112.8
1.01	8.36	86	8.60	0	75	29	112.8
1.01	8.42	87	8.70	0	73	28	112.7
1.01	8.48	88	8.80	0	71	28	112.7
1.01	8.54	89	8.90	0	69	27	112.7
1.01	9.00	90	9.00	0	67	26	112.7
1.01	9.06	91	9.10	0	65	26	112.7
1.01	9.12	92	9.20	0	63	25	112.6
1.01	9.18	93	9.30	0	62	25	112.6
1.01	9.24	94	9.40	0	60	24	112.6
1.01	9.30	95	9.50	0	58	24	112.6
1.01	9.36	96	9.60	0	56	23	112.6
1.01	9.42	97	9.70	0	55	23	112.5
1.01	9.48	98	9.80	0	53	22	112.5
1.01	9.54	99	9.90	0	52	22	112.5
1.01	10.00	100	10.00	0	50	22	112.5

PEAK OUTFLOW IS	321	AT TIME	4.30 HOURS				
CFS	321	176	111	111	11123		
CMS	9	5	3	3	315		
INCHES		3.28	3.45	3.45	3.45		
MM		83.29	87.60	87.60	87.60		
AC-FT		87	92	92	92		
THOUS CU M		108	113	113	113		

RUNOFF SUMMARY, AVERAGE FLOW IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)

	AREA IN SQUARE MILES(SQUARE KILOMETERS)									
HYDROGRAPH AT	1	1163	229	137		0.50				
	(32.94)	(6.48)	(3.89)	(3.89)	(1.29)
ROUTED TO	2	321	176	111	111	0.50				
	(9.08)	(4.99)	(3.15)	(3.15)	(1.29)
SUMMARY OF DAM SAFETY ANALYSIS										

SUMMARY OF DAM SAFETY ANALYSIS

	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM			
ELEVATION	111.70	111.70	115.00			
STORAGE	0	0	93			
OUTFLOW	0	0	481			
MAXIMUM	MAXIMUM	MAXIMUM	MAXIMUM	DURATION	TIME OF	TIME OF
RESERVOIR	DEPTH	STORAGE	OUTFLOW	OVER TOP	MAX OUTFLOW	FAILURE
W S ELEV	OVER DAM	AC-FT	CFS	HOURS	HOURS	HOURS
114.26	0.00	71	321	0.00	4.30	0.00

